

DEPARTMENT OF NATURAL RESOURCES AND ENVIRONMENTAL CONTROL
DIVISION OF WASTE AND HAZARDOUS SUBSTANCES

Statutory Authority: 7 Delaware Code, Chapters 60 and 74 and Section 6010(a) (7 **Del.C.** Chs. 60 & 74 & §6010(a))

7 DE Admin. Code 1351

ERRATA

1351 Underground Storage Tank Systems

* **Please Note:** The Department of Natural Resources and Environmental Control regulation, 7 **DE Admin. Code 1351** Underground Storage Tank Systems, was published as final in the *Delaware Register of Regulations*, 27 **DE Reg.** 533 (01/01/24). Subsections 1.13.7 (Part C) and 1.22.3.3 (Part B) were inadvertently published incorrectly.

Subsection 1.13.7 was published as:

1.13.7 During the installation of all new UST Systems, every stage of the construction shall be documented with photographs to demonstrate that the UST System was installed in compliance with the requirements for new UST Systems. Upon completion of the installation, copies of the photographs, as built plan, and required certification(s) as required in Part A, subsections 4.6.11 and 4.6.12 shall be submitted to the Department within ~~thirty (30)~~ 30 Days of the completion of the UST System installation. The Facility Owner and Operator shall keep copies of all documents and photographs on file for the life of the UST System.

Subsection 1.13.7 should have read:

1.13.7 During the installation of all new UST Systems, every stage of the construction shall be documented with photographs to demonstrate that the UST System was installed in compliance with the requirements for new UST Systems. Upon completion of the installation, copies of the photographs, as built plan, and required certification(s) as required in Part A, subsections 4.6.11 and 4.6.12 shall be submitted to the Department within ~~thirty (30)~~ 30 Days of the completion of the UST System installation. The **[Facility]** Owner and Operator shall keep copies of all documents and photographs on file for the life of the UST System.

Subsection 1.22.3.3 was published as:

1.22.3.3 Vent Line flow restrictors (ball float valves) shall not be installed for overfill prevention after ~~January 11, 2020~~.

Subsection 1.22.3.3 should have read:

1.22.3.3 Vent Line flow restrictors (ball float valves) shall not be installed for overfill prevention **[after]** ~~January 11, 2020~~.

27 DE Reg. 561 (02/01/24) (Errata)

